
\NOT USED NO SCALE



MaxWell IV Drainage System Detail And Specifications

1) MANHOLE CONE - MODIFIED FLAT

2 MOISTURE MEMBRANE - 6 MIL PLASTIC. PLACE SECURELY AGAINST CONE AND HOLE SIDEWALL.

(3) BOLTED RING & GRATE - CLEAN CAST IRON WITH WORDING "STORM WATER ONLY" IN RAISED LETTERS AND BOLTED IN TWO LOCATIONS, SECURED TO CONE WITH MORTAR. RIM ELEVATION ±0.02' OF

- (4) GRADED BASIN (BY OTHERS)
- 5 COMPACTED BASE MATERIAL (BY
- 6 PUREFLO DEBRIS SHIELD ROLLED 16 GA. STEEL X 24" LENGTH WITH VENTED ANTI-SIPHON AND INTERNAL .265" MAX. SWO FLATTENED EXPANDED STEEL SCREEN X 12" LENGTH. FUSION BONDED EPOXY COATED.
- 7 PRECAST LINER 4000 PSI CONCRETE 48" ID. 54" OD. CENTER IN HOLE AND ALIGN SECTIONS TO MAXIMIZE BEARING SURFACE.
- 8 MIN. 6' * DRILLED SHAFT.
- 9 SUPPORT BRACKET FORMED 12 GA. STEEL. FUSION BONDED EPOXY COATED.
- 10 OVERFLOW PIPE SCH 40 PVC MATED TO DRAINAGE PIPE BELOW BASE SEAL.
- 11 DRAINAGE PIPE ADS HIGHWAY GRADE WITH MDI-A COUPLER. SUSPEND PIPE DURING BACKFILL OPERATIONS TO PREVENT BUCKLING OR BREAKAGE.

12) BASE SEAL - GEOTEXTILE, POLY LINER OR CONCRETE SLURRY.


(13) ROCK - CLEAN AND WASHED. SIZED BETWEEN³/₈" AND 1-1/2",
TO BEST COMPLEMENT SOIL CONDITIONS. 24" * 3

(14) FLOFAST DRAINAGE SCREEN -SCHEDULE 40 PVC 0.120 SLOTTED WELL SCREEN WITH 32 SLOTS PER ROW/FT. 96" OVERALL LENGTH WITH MDI-B COUPLER.

(15) MIN. 4' DIA SHAFT - DRILLED IN A MANNER TO MAINTAIN PERMEABILIY OF DRAINAGE

- (16) FABRIC SEAL UV RESISTANT GEOTEXTILE - TO BE REMOVED BY CUSTOMER AT PROJECT COMPLETION.
- 17) ABSORBENT HYDROPHOBIC PETROCHEMICAL SPONGE. MIN. 100 OZ. CAPACITY.
- * FREEBOARD DEPTH VARIES WITH INLET PIPE ELEVATION. INCREASE INTERCEPTOR/SETTLING CHAMBER DEPTH AS NEEDED TO MAINTAIN ALL INLET PIPE ELEVATIONS ABOVE CONNECTOR PIPE OVERFLOW.

AZ LIC 70465 47067, ADWR 363 CA LIC 528080, HAZ NV LIV 35350





TORRENT

1509 East Elwood Street, Phoenix, AZ 85040 **RESOURCES**PHONE (602) 268-0785 FAX (602) 268-0820 CA (805) 947-9836 NV (702) 366-1234


SEE DRYWELL NOTE # 5<u>3"</u>














TER

Contact Arizona 811 at least two full working days before you begin excav Call 811 or click Arizona811.co

DP22-0122 C 15-22-01

HORIZ: N/A VERT : N/A SHEET 34 OF 86

\\cp.rickeng.com\projects\T_TUC_F\4329_Los_Reales_Alvernon_Property\Admin\SubmittalSets\Development Package-DP22-0122\Revision 1\2023_07_14 - Rev Storm Drain\TUC CorpStds 2005.dscript

\\cp.rickeng.com\projects\T_TUC_F\4329_Los_Reales_Alvernon_Property\Civil\PHASE 1\4329APH1dp34.dgn

07-AUG-2023